

क्षेत्रीय जैवप्रौद्योगिकी केन्द्र

Regional Centre for Biotechnology

राष्ट्रीय महत्ता की संस्था

An institution of National Importance

(यूनेस्को के तत्वावधान में जैव प्रौद्योगिकी विभाग, भारत सरकार द्वारा स्थापित)
(Established by the Dept of Biotechnology, Govt of India under the auspices of UNESCO)

Ref: RCB/NIQ/02/2022-23/IT

Date 20.05.2022

Regional Centre for Biotechnology (RCB), an 'Institution of National Importance' providing education, training and research is established by the Department of Biotechnology, Government of India under the auspices of UNESCO. On behalf of Executive Director, Regional Centre for Biotechnology, sealed quotations are invited from agencies for providing LAN infrastructure at Bioinformatics Centre as per BoQ and terms and conditions appended below:

S.No.	Product Description	Make	Qty	
A	Passive Components			
Copper Components				
	Category 6/ Class E Solid Cable, 4 Pair , 305 Mtrs Roll	D-Link	1	Box
	Category 6/ Class E UTP 24 port Patch Panel with Inbuilt Wire manager loaded	D-Link	1	No's
	Class E/Category 6 UTP Keystone Jack, Color Blue For Data(user side)	D-Link	16	No's
	86 x 86 mm, Dual Faceplate accepts two Keystone Jacks	D-Link	16	No's
	86 x 86 x 32mm Back Box for Single and Dual Faceplate	D-Link	16	No's
	Class E/Category 6 UTP 24AWG Patch Cord, 1M, color Blue For Data (Rack End)	D-Link	16	No's
	Class E/Category 6 UTP 24AWG Patch Cord, 2M, color Blue For Data (User End)	D-Link	16	No's
B	Active Components			
Switch Components				
	24 Port PoE Switch with 1G port and uplink port 10g	OEM	1	No's
	MM SFP Module 10 G	OEM	2	No's
C	Fibre Components			
	6 Core Fiber Cable , MM	D-Link	50	Mtr's
	6 Port Fully Loaded LIU With LC Port	D-Link	1	No's
	LC -LC Fiber Patch Cord 3 meter	D-Link	2	No's
D	Consumable and Accessories Components			
Consumable Components				
	12" Inch White Nylon Zip Wire Organizer / Self Locking Tie (100 Pcs)	OEM	1	Pkts
	PVC Tube 7 mm ID for Laser Printed Ferrules	OEM	32	No's
	Sticker Labelling sheet (Black Print on White paper) For Laser Printed Labels for Jack Panel, Face Plate & LIU	Dymo	2	No's
	25/32mm PVC Conduit \ Casing Capping \ Flexible Pipe With all Supporting Accessories	OEM	77	Mtrs
	One PVC Cable Manager	Perfect Rack	1	No's

Two Hardware Packet	Perfect Rack	1	No's
E Services and Support Components			
Professional Installation Components			
Pulling/Laying of UTP Cable	BGL	305	Mtrs
Multi point termination of UTP cable including identification, both end termination, labelling, patching & dressing of Copper Patch cords with consumables and Fixing/Labelling of Jack Panel, Cable Manager, & Face Plate	BGL	16	Nodes
Testing of UTP Cables as per standards with LAN Tester	BGL	16	No's
Laying of PVC Conduit & Casing Capping	BGL	77	Mtrs
Installation, Configuration, Commissioning & Testing of Access Switch	BGL	1	No's

Terms & conditions

- (i) Active Components must be Make in India.
- (ii) The Quality of Cables and others accessories should be as per OEM standards and same will be verified by the authorised officer of RCB.
- (iii) After successful deployment the vendor has to perform testing of all the active components.
- (iv) Delivery and installation must be completed within 45 days.
- (v) Warranty and support shall be up to 1 year.
- (vi) The work shall be completed as per Schedule of Work, specification and instruction of System Administrator
- (vii) No Advance payment shall be made.
- (viii) Payment will be made as per actual work done.
- (ix) Triplicate pre-receipted invoice should be submitted by agency with revenue ticket of ₹1/-.
- (x) The rates are all inclusive of material, labour, freight, cartage, loading-unloading and applicable GST etc.
- (xi) Sealed quotations shall be submitted directly in the box kept at RCB reception or sent through speed post/courier so as to reach RCB latest by 1500 Hrs on 31.05.2022. Address of Speed post/Courier is: The Executive Director, Regional Centre for Biotechnology, NCR Biotech Science Cluster, 2nd Mile Stone, Faridabad-Gurugram Expressway, Faridabad, Haryana-121001.
- (xii) The Sealed envelope shall be super scribed as "Quotation for providing LAN infrastructure at Bioinformatics Centre, NIQ No. RCB/NIQ/02/2022-23/IT".
- (xiii) The quantity as shown above is tentative and may be increased or decreased at same rates upto 10% based on the actual usage.

(Signature and stamp of the bidder)

क्षेत्रीय जैवप्रौद्योगिकी केन्द्र

Regional Centre for Biotechnology

राष्ट्रीय महत्ता की संस्था

An institution of National Importance

(यूनेस्को के तत्वावधान में जैव प्रौद्योगिकी विभाग, भारत सरकार द्वारा स्थापित)
(Established by the Dept of Biotechnology, Govt of India under the auspices of UNESCO)

Ref: RCB/NIQ/02/2022-23/CA

Date:

Quotation

S.No.	Product Description	Make	Qty	Rate	Amount
A	Passive Components				
Copper Components					
	Category 6/ Class E Solid Cable, 4 Pair , 305 Mtrs Roll	D-Link	1	Box	
	Category 6/ Class E UTP 24 port Patch Panel with Inbuilt Wire manager loaded	D-Link	1	No's	
	Class E/Category 6 UTP Keystone Jack, Color Blue For Data(user side)	D-Link	16	No's	
	86 x 86 mm, Dual Faceplate accepts two Keystone Jacks	D-Link	16	No's	
	86 x 86 x 32mm Back Box for Single and Dual Faceplate	D-Link	16	No's	
	Class E/Category 6 UTP 24AWG Patch Cord, 1M, color Blue For Data (Rack End)	D-Link	16	No's	
	Class E/Category 6 UTP 24AWG Patch Cord, 2M, color Blue For Data (User End)	D-Link	16	No's	
B	Active Components				
Switch Components					
	24 Port PoE Switch with 1G port and uplink port 10g	OEM	1	No's	
	MM SFP Module 10 G	OEM	2	No's	
C	Fibre Components				
	6 Core Fiber Cable , MM	D-Link	50	Mtr's	
	6 Port Fully Loaded LIU With LC Port	D-Link	1	No's	
	LC -LC Fiber Patch Cord 3 meter	D-Link	2	No's	
D	Consumable and Accessories Components				
Consumable Components					
	12" Inch White Nylon Zip Wire Organizer / Self Locking Tie (100 Pcs)	OEM	1	Pkts	
	PVC Tube 7 mm ID for Laser Printed Ferrules	OEM	32	No's	
	Sticker Labelling sheet (Black Print on White paper) For Laser Printed	Dymo	2	No's	

Labels for Jack Panel, Face Plate & LIU					
25/32mm PVC Conduit \ Casing Capping \ Flexible Pipe With all Supporting Accessories	OEM	77	Mtrs		
One PVC Cable Manager	Perfect Rack	1	No's		
Two Hardware Packet	Perfect Rack	1	No's		
E	Services and Support Components				
Professional Installation Components					
Pulling/Laying of UTP Cable	BGL	305	Mtrs		
Multi point termination of UTP cable including identification, both end termination, labelling, patching & dressing of Copper Patch cords with consumables and Fixing/Labelling of Jack Panel, Cable Manager, & Face Plate	BGL	16	Nodes		
Testing of UTP Cables as per standards with LAN Tester	BGL	16	No's		
Laying of PVC Conduit & Casing Capping	BGL	77	Mtrs		
Installation, Configuration, Commissioning & Testing of Access Switch	BGL	1	No's		
				Sub Total	
				GST	
				Grand Total	

(Signature Name and Stamp of the bidder)